

Attachment A- Bid Sheet
Christmas Lighting and Decoration Products and Services
Downtown - Including Installation, Maintenance, and Removal

No.	Description	Specifications	Estimated Quantity	Cost Per Unit (tree, foot, etc.)	Total
1	Install/remove lights in trees (trunks, branches, canopies).	The bidder will install/remove, per tree, an average of 12,000 warm white 5mm LED lights with 4" bulb spacing on green wire installed on the trunk and branches at a 4" spaced wrap and installed in the leaves on the outer canopy of the tree. Note: In 2017 the largest tree took 16,000 lights to light the trunk, branches and canopy.	13 trees		
2	Install/remove lighted garland on lamp posts.	The bidder will install/remove garland with a minimum of 14" wide green LED lit artificial pine branch garland with no fewer than 250 tips per 9'.	18 posts		
3	Install/remove ornamented garland on lamp posts in Pine Street parking lot.	The bidder will install/remove ornamented garland that will be wrapped around the lamp posts with spacing no more than 4 feet between wraps.	15 posts		

Fisherman's Park/June Hill Pape Riverwalk - Including Installation, Maintenance, and Removal

No.	Description	Specifications	Estimated Quantity	Cost Per Unit (tree, foot, etc.)	Total
1	Install/remove lights on pipe railing and fencing.	The bidder will install/remove lights on all pipe fencing/railing. It will be wrapped in warm white LED lights. The bulbs are to be 5mm, concave and spaced no more than 4 inches apart. The spacing between wraps are to be no more than 4" apart. Most of the fencing/railing is located within the main area of the park. This also include the stairway entrances behind the Bastrop Public Library, Wells Fargo, and Ferry Park. NOTE: For railings that have 3 sections & 3 horizontal rails per section, only the bottom 2 rails and outermost of each section will be wrapped.	12,000 feet		
2	Install/remove lights on black iron fencing.	The bidder will install/remove lights on a section of black iron fencing halfway down the Riverwalk. The top and bottom horizontal rails will be wrapped in warm white LED lights. The bulbs are to be 5mm, concave and spaced no more than 4" apart. The spacing between wraps will be no more than 4" apart, or at least 1 wrap in between vertical rails.	850 feet		
3	Install/remove light wraps on trees inside the park and along the Riverwalk.	The bidder will install/remove lights in designated trees in the park and along the Riverwalk. These trees will be wrapped 14' high in warm white LED lights. This includes from base of the trunk and all branches up to the 14' mark. The bulbs are to be 5mm, concave and spaced no more than 4" apart. The spacing between wraps are to be no more than 4" apart. These trees will be marked at the base with white paint.	65 trees		
4	Install/remove light wraps/drops on trees along the Riverwalk	The bidder will install/remove lights in designated trees along the Riverwalk. These trees will be wrapped 14' high in warm white LED lights and will include blinking light drops. This includes the base of the trunk and all branches up to the 14' mark. The bulbs are to be 5mm, concave and spaced no more than 4" apart. The spacing between wraps are to be no more than 4" apart. The light drops shall not exceed 20' in length and shall be at a reasonable height above the ground. Trees will be marked at the base with blue paint.	25 trees		
5	Install/remove lighted garland on lamp posts in the park and along the Riverwalk.	The bidder will install/remove garland with a minimum of 14" wide green LED lit artificial pine branch garland with no fewer than 250 tips per 9'. Each will include outdoor nylon 18" red structural bows at the top of the light poles.	42 posts		
6	Install/remove lighted garland on overlooks along the Riverwalk.	The bidder will install/remove garland with warm white LED lights that will be fixed in a method in the bidders best judgment along the top railing of each of the overlooks.	2 overlooks		
7	Install/remove tree of lights	The bidder will install/remove 12' tree of lights in the park. The spots will be identified before the time of installation.	3 trees		
8	Install/remove large Christmas tree	The bidder will install/remove a 24' branched frame tree that is warm white LED lighted and ornamented. It will include a 3' star topper.	1 tree		

LIGHT TUNNEL: Fisherman's Park/June Hill Pape Riverwalk - Including Installation, Maintenance, and Removal

OPTIONAL BID: This option is separate and apart from the base bid and will be awarded separately, if chosen by the City.

No.	Description	Specifications	Estimated Quantity	Cost Per Unit (tree, foot, etc.)	Total
1	Lighted tunnel to be placed in either Fisherman's Park or along the June Pape Riverwalk. (TBD)	3-D round tunnel with aluminum frame with LED lights.	50 feet		

COMPANY NAME: _____

SIGNATURE OF AUTHORIZED REPRESENTATIVE: _____

PRINTED NAME: _____

EMAIL ADDRESS: _____

*By the signature hereon affixed, the bidder hereby certifies that neither the bidder nor the entity represented by the bidder, or anyone acting for such entity has violated the antitrust laws of this State, codified in Section 15.01 et seq., Texas Business and Commerce Code, or the